BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/OW/WORK_INDENT24474

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Construction of cement concrete road and improvements to drain in BB nagara and Maruthinagara in ward no. 8, Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N VENKATA REDDY	
				In Figures	In Words
1	260	Removing B.S slab of drain and stacking	sqm	63.72	Rupees Sixty Three and Seventy Two Paise Only
2	286	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	cum	83.16	Rupees Eighty Three and Sixteen Paise Only
3	42.9	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement 220kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @o.465 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5236.92	Rupees Five Thousand Two Hundred Thirty Six and Ninety Two Paise Only
4	111.15	Providing laying plain/ reinforced cement concrete for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc.complete as per approved drawing and design MORTH specification No.1500, 1700, 2200. M20 Grade using Concrete mixer	cum	5581.0	Rupees Five Thousand Five Hundred Eighty One Only
5	7.22	Providing T.M.Tsteel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members whereever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	45477.0	Rupees Forty Five Thousand Four Hundred Seventy Seven Only
6	286	Providing and fixing RCC 1:2:4 Precast slab for covrering using 20mm and Downsize granite jelly as per design including necessary centering, forming, Curing and finishing with CM 1:3 etc complete 250mm thick	sqm	5111.0	Rupees Five Thousand One Hundred Eleven Only
7	361	Lead for disposal of debris shall be payable at carrage rates by mechanical means including loading and unloading From 13.30 Kms	cum	123.2	Rupees One Hundred Twenty Three and Twenty Paise Only

Signature of the Contractor

19/04

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

19/04